United States Department of the Interior Heritage Conservation and Recreation Service

National Register of Historic Places Inventory—Nomination Form

See instructions in *How to Complete National Register Forms* Type all entries—complete applicable sections

For HCRS use only received date entered

1. Nan	16							
historic	Cathedral of	the Im	maculate	Conceptio	on			
and/or common							d un to	Pour Territ
2. Loca	ation						,	
street & number	. Cathedral Sq	uare, J	efferson	at Calhou	un Streets		not for p	ublication
city, town	Fort Wayne		vic	inity of	congressio	nal district	Four	th
state	Indiana	code	018	county	Allen		со	de 003
3. Clas	sificatio	n		MODES SECTIONS OF CONTRACT SHOULD MODE OF CONTRACT SHOULD SHOW THE SECTION SHOULD SHOW THE SECTION SHOWS SHOW THE				
Category district _X_ building(s) structure site object	Ownership public private both Public Acquisit in process being consid		X occupie	ipied progress stricted		ulture nercial ational tainment nment trial	_X relig	nte residence ious ntific sportation
street & number	P.O. Box 390	rort w	ayne - So	ith Bend	r Roma = Panasa			
city, town	Fort Wayne		vic	inity of	onr as o	state	Indiana	
5. Loca	ation of L	.ega	l Desc	riptic	on			
courthouse, regi	stry of deeds, etc.	Allen	County Co	urthouse,	, Wayne Twp	. Assess	or's Offic	ce
street & number		1 Main	Street					
city, town		Fort W	ayne			state	Indiana	46802
6. Rep	resentati	on i	n Exis	ting !	Survey	\$		
Indiana H title Structure	Historic Sites es Inventory	and		nas this pro	perty been det	ermined el	legible?	yes X n
date 1979			lan angri lan sel	o noro es one eooli	federa	ıl X sta	tecour	ityloca
depository for su	rvey records Inc	diana De	epartment	of Natur	al Resourc	es	36 gasa	
city, town Indi	anapolis					state	Indiana	

7. Description

Condition X excellent good	deteriorated ruins	Check one unaltered X altered	Check one X original site moved date
fair	unexposed		

Describe the present and original (if known) physical appearance

The Fort Wayne Cathedral of the Immaculate Conception is the oldest church building in existence today in Fort Wayne, Indiana. During the course of the last 119 years, this Cathedral has undergone a number of renovations both on the interior and exterior. Basically speaking, it is a Gothic structure, one hundred and eighty feet long and eighty feet wide, with twin towers in the facade flanking the main portal. Originally, the building was of red brick trimmed with gray sandstone. These materials are presently covered over with stone.

The vaulted ceiling of the Cathedral is supported by fourteen clustered columns set twenty-two feet apart. The sanctuary is thirty-four feet deep and thirty-six feet wide. The cost of the church, exclusive of pews, organ and altars, was \$54.000. The organ cost \$3,000; the main altar, \$1,200; the pulpit, \$1,000; and the bishop's throne, \$700. The large candlesticks, which are still in use on the main altar, were made to order for the Fort Wayne Cathedral by a group of nuns in France at a cost of 4,500 francs. An exact facsimile of these candlesticks was later placed in the famous Church of the Magdalena in Paris. Of the money raised for the Cathedral's construction, more than \$46,000 was raised by Father Julian Benoit, the architect, on his own initiative.

The Cathedral has experienced a number of interior changes, but structurally has remained the same. In the years 1896 and 1897, the present Bavarian stained glass windows were installed. All fourteen of these windows were created by F. X. Zettler, at the Royal Bavarian Art Institute for Stained Glass in Munich, Germany. All fourteen windows (seven on each side) are dedicated to a scene in the life of Mary, in honor of whom the Cathedral is named. These windows are considered to be the best examples of this type of stained glass in the entire Western Hemisphere. A recent appraisal of these fourteen windows valued each of them in excess of \$25,000. Their original cost is unknown. Also between the years 1896 and 1897, the first of this Cathedral's now famous wood carvings were installed. The fourteen Stations of the Cross, all dedicated to a scene in the life of Christ, were hand-carved in Germany and brought to this country especially for this church. During this time, too, the solid marble communion railing was installed.

In 1906, improvements were made to the crypt (located directly under the sanctuary) in order to provide a suitable burial place for church dignitaries. At present, the first four bishops of the Diocese and three of the Cathedral's rectors are buried there.

Between the years of 1925 and 1935, A. M. Mowat, of New York, Chicago and Paris, designed the now world-famous hand-carved sanctuary depicting the Redemption of Mankind. The actual wood carvings were done by two men brought over from the wood-carving capital of the world, Oberammergau, Germany. Installed were a light oak hand-carved reredos, altars, statues, panels and a bishop's throne. These wood carvings have been said to be the best example of the wood carvers' art in the entire United States. During this renovation period, too, the Cathedral was given a new terrazzo floor, laid over the original floor, new pews to match the Gothic elegance of the church, electric chandeliers, a new organ and carillon.

Following World War II, the present three pipe organs were installed. In 1948, the side altars were moved to their present positions and the choir/clergy stalls were installed. In 1960, the pulpit was lowered from its front pillared location and placed on the floor of the sanctuary. At this same time, the communion railing was lowered to one step above floor level, thereby providing a better overall view of the sanctuary from the nave. In

8. Significance

1400-1499 1500-1599 1600-1699 1700-1799 X 1800-1899	v -	community planning conservation economics education engineering exploration/settleme	landscape architectur law literature military music	science sculpture social/ humanitarian theater
Specific dates	1859-1860	Builder/Architect Arc	chitect: Rev. Msgr. Ju	lian Benoit

Statement of Significance (in one paragraph)

Both the Cathedral of the Immaculate Conception and the site upon which the church is located have great historical and architectural significance for Fort Wayne and northern Indiana. Architecturally, the building is a fine example of the Gothic style. The stained glass windows, dating from the late nineteenth century, and the interior wood carvings, dating from the late nineteenth and early twentieth centuries, are considered to be among the most beautiful examples of both crafts in the western hemisphere. Also, the site was a burial ground for the Miami Indians, a tribe once powerful in the area. The first Catholic church, rectory, school, and cemetery in northern Indiana were built on the site. The present Cathedral is the oldest church building in the city of Fort Wayne.

In 1831, Father Stephen Badin, later instrumental in founding the University of Notre Dame at South Bend, assisted the Catholic families around Fort Wayne in purchasing land for a church. The first building was a temporary log structure erected in 1835. The Catholic community erected the first permanent church, also built of logs, in 1837. Successive land purchases allowed the size of the site to expand and a cemetery (1840), and school (1845), and rectory (1853-54) were added to the church square.

In 1846, Father Julian Benoit interceded between the remaining Miami Indians and the United States government, which had ordered their removal to a reservation in Kansas. At Father Benoit's urging, Chief LaFontaine consented to be removed. The Miami burial ground in Fort Wayne, however, remained behind and is now part of the Cathedral square. Jean-Baptiste Richardville, a Miami chief and descendant of one of the most important French families in the Old Northwest, the Drouet de Richerville family, is buried there. A stone marker, erected by the Daughters of the American Revolution, marks the Richardville grave.

On September 22, 1857, the Vatican established the Diocese of Fort Wayne, thereby necessitating the building of a cathedral church. Late in that year, Father Benoit had the original log church moved to the east side of the square. Fort Wayne's first bishop, the Most Reverend John H. Luers, laid the cornerstone on June 19, 1859. The cathedral took eighteen months to build and was dedicated in December, 1860.

The Cathedral of the Immaculate Conception is an architectural masterpiece. The present Bavarian stained glass windows are considered to be among the best examples of this type of stained glass in the western hemisphere. Its wood carvings, executed by German craftsmen, are excellent examples of the wood carvers' art. The Fort Wayne Sentinel of October 20, 1860, stated that "this magnificent edifice ... is one of the finest on the continent and altogether, the grandest church structure in the West."

United States Department of the Interior Heritage Conservation and Recreation Service

National Register of Historic Places Inventory—Nomination Form

For HCRS use only received date entered

Continuation sheet

Item number

Page

1965, in order to comply with the guidelines set forth by the Second Vatican Council, a new portable altar was installed in order to say Mass facing the people. The stone and marble altar installed during the early part of the century was not removed, however, and is still in place today. Finally in 1974, a new pulpit was installed (made from wood salvaged from some of the choir/clergy stalls), thereby completing the total use of wood in the sanctuary.

Exterior

The Cathedral was originally of red brick trimmed with gray sandstone. Its architect, being a Frenchman, designed a Cathedral which was French Gothic in appearance. By the early 1900s, however, the original red brick was beginning to corrode, and between 1910 and 1921, this red brick was covered with imitation rock. At this time the north sacristy was enlarged by the addition of a second floor. In 1924, the south sacristy was also enlarged and two small side wings were added to the east end of the Cathedral, forming an abbreviated transept which provides side entrances. In 1935, the slates were removed from the two spires and replaced with copper which remains to this day.

Shortly after World War II, the imitation rock which covered the Cathedral was beginning to disintegrate and fall off in large sections. Thus in 1949-50, the exterior of the entire Cathedral was refaced with Indiana Limestone and Wisconsin Lannonstone. During this renovation, the exterior of the Cathedral was somewhat altered. The French Gothic designs of its architect, Father Benoit, gave way to the more streamlined ways of German Gothic, in order to better harmonize the Cathedral with the ultra-modern designs of the Chapel and Diocesan Chancery which were being built on the Square at that time. The pinnacles and parapets were removed from the towers. The twentyeight foot stained glass windows in front were reduced in size and the tiers of ventilators on the upper part of the towers were changed. The small rose window high up on the center of the facade was taken out, filled in and covered with stone. The tracery around the niche, above the main entrance, was simplified and the statue of the Immaculate Conception in this niche was refinished. A new double door of glass and bronze was set in the main entrance. The old stone steps were removed and broader ones were installed. The plaza was redesigned with a new curved double walk forming a semi-circle to Calhoun Street and bordered by a low wall of limestone and lannonstone in descending tiers.

9. Major Bibliographical References

See Continuation Sheet.

10. Geographical Data	
Acreage of nominated property Less than one acre Quadrangle name Fort Wayne West, Indiana UMT References	Quadrangle scale 1:24,000
A 1,6 6 5,6 4,4 0 4,5 4,8 6,2 0 Zone Easting Northing C	Zone Easting Northing D
Verbal boundary description and justification	
Lot 271 of Cathedral Square	
List all states and counties for properties overlapp	oing state or county boundaries
state code	county code
state code	county code
11. Form Prepared By	
Mara Anna Dilau	
and the second second and the second	Contombon 1070
organization	date September 1978
street & number 2100 St. Mary's Avenue, Apt.	226 telephone 219-743-1401
city or town Fort Wayne	state Indiana
12. State Historic Preser	vation Officer Certification
The evaluated significance of this property within the state	e is:
national state X	local
As the designated State Historic Preservation Officer for the 665), I hereby nominate this property for inclusion in the Naccording to the criteria and procedures set to the by the H	he National Historic Preservation Act of 1966 (Public Law 89– lational Register and certify that it has been evaluated leritage Conservation and Recreation Service.
State Historic Preservation Officer signature	ephilloud
title State Historic Preservation Officer	date August 6, 1980
For HCRS use only I hereby certify that this property is included in the N	lational Register
	date
Keeper of the National Register	
Attest:	date
Chief of Registration	

United States Department of the Interior Heritage Conservation and Recreation Service

National Register of Historic Places Inventory—Nomination Form

For HCRS use only received date entered

Continuation sheet

Item number

Page 2

REFERENCES

History of Allen County, Indiana. Chicago: Kingman Bros., 1880.

Alerding, H. J.

The Diocese of Fort Wayne, Vol. 1 Fort Wayne: The Archer Printing Co., 1907.

Noll, J. F.

The Diocese of Fort Wayne, Vol. 2 Fort Wayne: 1941.

41.

The Catholic Church in Fort Wayne. Fort Wayne Allen County-Fort Wayne Historical Society, Public Library of Fort Wayne and Allan County, 1961.

Poinsatte, C. R.

Fort Wayne During the Canal Era, 1828-1855. Indiana Historical Bureau, 1969.

Mobile Travel Guide, Great Lakes Area. New York: Rand McNally & Co., 1973.

Ankenbruck, John

Twentieth Century History of Fort Wayne. Fort Wayne: 20th Century Historical Fort Wayne Inc., 1975.


Griswold, B. J.

The Pictorial History of Fort Wayne, Indiana. Chicago: Robert O. Law Co., 1917.

Blanchard, Charles

History of the Catholic Church in Indiana. Logansport: A. W. Bowen & Co., 1898.

American Auto Association Tourbook. Falls Church: American Auto Association Press, 1978.



Cathedral of the Immaculate Conception

Fort Wayne, Indiana

UTM Reference: 16/656440/4548620